

Republic of the Philippines
Province of Sorsogon
MUNICIPALITY OF DONSOL
MUNICIPAL ENGINEERING OFFICE

PROGRAM OF WORKS
(SAMPLE)

PROJECT NAME : Concreting of Barangay Road
LOCATION : Purok 3, Barangay Ogod, Donsol, Sorsogon
PROJECT LENGTH : 200.00 linear meters x 4.00 m width (800.00 sq.m)
PAVEMENT THK : 0.23 m Portland Cement Concrete Pavement (PCCP)
SOURCE OF FUND : 20% Development Fund, CY 2026
MODE OF IMPL. : By Contract (Public Bidding)
DURATION : Sixty (60) Calendar Days
DATE PREPARED : October 4, 2026

I. SCOPE OF WORK / BILL OF QUANTITIES

ITEM NO.	DESCRIPTION	QTY	UNIT	UNIT COST	AMOUNT
B.5	Project Billboard / Signboard	1	each	5,000.00	5,000.00
B.7	Occupational Safety and Health Program	1	lot	25,000.00	25,000.00
B.9	Mobilization / Demobilization	1	lot	30,000.00	30,000.00
100(1)	Clearing and Grubbing	800	sq.m	25.00	20,000.00
105(1)a	Subgrade Preparation (Common Material)	800	sq.m	45.00	36,000.00
200(1)	Aggregate Subbase Course	120	cu.m	1,450.00	174,000.00
311(1)c	PCCP (Unreinforced) 0.23m thk, 14-day	800	sq.m	1,750.00	1,400,000.00
TOTAL ESTIMATED DIRECT COST					1,690,000.00

II. SUMMARY OF COST

A. Total Estimated Direct Cost (EDC)	PHP	1,690,000.00
B. Overhead, Contingencies & Misc. (8% of EDC)		135,200.00
C. Contractor's Profit (8% of EDC)		135,200.00
D. Value Added Tax (5% of A+B+C)		98,020.00
Total Indirect Cost (B+C+D)		368,420.00
TOTAL ESTIMATED PROJECT COST (ABC)		PHP 2,058,420.00

III. WORK SCHEDULE AND WEIGHT OF ACTIVITIES (basis of progress billing)

ITEM NO.	WEIGHT %	WK 1-2	WK 3-4	WK 5-6	WK 7-8	WK 9
B.5	0.30	0.30	-	-	-	-
B.7	1.48	0.30	0.30	0.30	0.30	0.30
B.9	1.78	0.89	-	-	-	0.89
100(1)	1.18	1.18	-	-	-	-
105(1)a	2.13	1.28	0.85	-	-	-
200(1)	10.30	-	7.21	3.09	-	-
311(1)c	82.84	-	-	28.99	37.28	16.57
PERIOD %	100.00	3.94	8.36	32.38	37.57	17.75
CUMUL. %		3.94	12.30	44.67	82.25	100.00

IV. MAJOR MATERIALS (estimated)

Portland Cement (40 kg)	1,680 bags
Fine Aggregate (Sand)	104 cu.m
Coarse Aggregate (Gravel 3/4")	192 cu.m
Aggregate Subbase Course	132 cu.m (incl. 10% compaction allowance)
Dowel / Tie Bars (16mm dia.)	120 pcs
Asphalt Sealant (joint filler)	4 pails

V. MANPOWER AND EQUIPMENT REQUIREMENTS

Manpower : 1 Project Engineer, 1 Foreman, 1 Safety Officer,
4 Skilled Workers, 10 Laborers
Equipment: 1 Backhoe, 1 Road Grader, 1 Vibratory Roller, 1 Water Truck,
2 One-Bagger Concrete Mixers, 2 Concrete Vibrators, 2 Dump Trucks

VI. NOTES

- Unit costs are based on prevailing market prices in Sorsogon Province.
- Concrete shall attain a minimum flexural strength of 3.8 MPa at 14 days.
- Progress billing shall be based on the activity weights in Part III.
- This is a SAMPLE document for reference only; figures are illustrative.

Prepared by:

Checked by:

[Name], Engineer II
Municipal Engineering Office

[Name], Municipal Engineer
Municipal Engineering Office

Reviewed / Recommending Approval:

Approved by:

[Name], MPDC
Municipal Planning & Dev. Office

[Name], Municipal Mayor
Municipality of Donsol